

REDLINE

Single Drive Roller

DRS260DS

Technical Data



Weight

Operating Mass	26,200 kg
Max. Operating Mass	26,300 kg
Module Mass (Front/Rear)	13,100kg/13,100 kg

Compaction

Static Linear Load	620 N/cm
Nominal Amplitude (High/Low)	2.0 mm/1.3 mm
Vibration Frequency (High/Low)	30 Hz/31 Hz
Centrifugal Force (High/Low)	410 kN/290 kN

Engine



Manufacturer/Model	DCEC B5.9 CS 4 220C
Type	6 缸 水冷
Rated Power	162kW @ 2,200 rpm
Electrical System	24V
Fuel Tank Capacity	300L

Traction

Speed Range	0-4.2/0-10km/h
Max. Theoretical Gradeability	40 %

尺寸Dimensions

α.Steering Angle	+/- 30°
A. Wheelbase	3,600 mm
W1. Front Overall Width	2,360 mm
W2. Drum Width	2,130 mm
W3. Rear Overall Width	2,160 mm
H. Overall Height	3,150 mm
D. Drum Diameter	1,570 mm
K. Front Minimum Ground Clearance	385 mm
K1. Minimum Ground Clearance	400 mm
S. Drum Shell Thickness	46 mm
L. Overall Length	7,190 mm
R2. Outside Turning Radius	7,830 mm



We reserve the right to modify product specifications without prior notice. All photos and illustrations are for reference only and may not fully represent the actual equipment.